

OUTSIDE

Walk the site: Check for tire hazards, obstacles for slides, where hook ups are located etc.

Turn off the breaker at the pedestal

Plug in your surge protector to the pedestal and wait for all clear

Park the trailer

Level left to right

Chock tires

Unhitch Truck

Turn batteries on

Level Trailer front to back

Deploy Stabilizers

Attach water pressure regulator

Connect to water (use filter)

Attach sewer hose (VERIFY the black tank is closed and check for leaks with gray water line)

Hook up power

Check Slide to make sure it is all clear (inside and out) then open.

Turn on propane

INSIDE

Turn on water heater & fridge (depending on hook ups)

Remove rods from fridge

Straighten anything that's out of place

Turn on AC/Heater if applicable

Put door mat out

THIS LIST IS JUST A GUIDELINE

Disclaimer: Your RV may have other steps necessary to ensure safety of you and your equipment, use list at your own risk If you have questions about your rig please ask the appropriate professionals**